

AD-A142 917


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
PUTMAN RESERVOIR DAM (U) CORPS OF ENGINEERS WALTHAM
MA NEW ENGLAND DIV AUG 78


1/1

UNCLASSIFIED

F/G 13/13

NL





AD-A142 917

CONNECTICUT WESTERN COASTAL AREA
GREENWICH, CONNECTICUT

PUTNAM RESERVOIR DAM
CT 00041

PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154

AUGUST 1978

84 07 02 040

DTIC FILE COPY

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER CT 00041	2. GOVT ACCESSION NO. AD-A142917	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Conn. Western Coastal Area Greenwich, Conn., Putnam Reservoir Dam NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE August 1978
		13. NUMBER OF PAGES 90
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Conn. Western Coastal Area Greenwich, Conn. Putnam Reservoir Dam		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) Putnam Reservoir dam consists of a rolled earth embankment with a concrete core wall, built originally in 1893 and modified in 1906 and 1922. The dam section is 640 ft. long with a maximum height of 35 ft. The spillway is 55 ft. long with an "Ogee" crest. The maximum spillway capacity at top of dam is 35 per cent of the peak inflow rate of the test flood. Therefore, the test flood cannot be passed by the spillway without overtopping the dam. The overflow will be 1.1 ft. above the top of the dam.		



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02154

REPLY TO
ATTENTION OF

NEDED

JAN 20 1979

Honorable Ella T. Grasso
Governor of the State of Connecticut
State Capitol
Hartford, Connecticut 06115

Dear Governor Grasso:


I am forwarding to you a copy of the Putnam Reservoir Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Department of Environmental Protection, the cooperating agency for the State of Connecticut. In addition, a copy of the report has also been furnished the owner, the Connecticut-American Waterworks Company, Inc., Greenwich, Connecticut 06830.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Department of Environmental Protection for your cooperation in carrying out this program.

Sincerely yours,


JOHN P. CHANDLER
Colonel, Corps of Engineers
Division Engineer

Incl
As stated

PUTNAM RESERVOIR DAM

CT 00041

CONNECTICUT WESTERN COASTAL AREA

GREENWICH, CONNECTICUT



PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM

Accession For	
NTIS	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	<input type="checkbox"/>
By _____	
Distribution _____	
Availability _____	
Dist	Avail for
A-1	1

PHASE I REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam: PUTNAM RESERVOIR DAM

State Located: Connecticut

County Located: Fairfield County

Stream: Horseneck Brook

Date of Inspection: 1 JUNE 1978

BRIEF ASSESSMENT

Putnam Reservoir dam consists of a rolled earth embankment with a concrete core wall, built originally in 1893 and modified in 1906 and 1922. The dam section is 640 feet long with a maximum height of 35 feet. The spillway is 55 feet long with an "Ogee" crest.

Based on the visual inspection of the site, review of available information and past performance of the dam, the dam is judged to be in good condition.

The maximum spillway capacity at top of dam is 35 per cent of the peak inflow rate of the test flood. Therefore, the test flood cannot be passed by the spillway without overtopping the dam. The overflow will be 1.1 feet above the top of the dam.

It is recommended that detailed investigations be undertaken by the owner to determine the requirements and methods for obtaining additional spillway capacity. Additionally, surface spalling and cracking of the spillway should be repaired in order to prevent continued deterioration and a potentially hazardous condition. In addition to establishing a program of periodic inspections during times of unusually high runoff, an around the clock surveillance and warning program should be established and exercised by the owner.



S. Giavara, P.E.
Principal

Registered, CT 7634


This Phase I Inspection Report on Putnam Reservoir Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.



CHARLES G. TIERSCH, Chairman
Chief, Foundation and Materials Branch
Engineering Division




FRED J. RAVENS, Jr., Member
Chief, Design Branch
Engineering Division



SAUL COOPER, Member
Chief, Water Control Branch
Engineering Division

APPROVAL RECOMMENDED:



JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
Colonel's Signature Page	
Brief Assessment	
Review Board Page	
Preface	i
Table of Contents	ii - iv
Overview Photo	v
Location Map	vi
 1. PROJECT INFORMATION	
1.1 General	1
a. Authority	1
b. Purpose of Inspection	1
1.2 Description of Project	1
a. Description of Dam and Appurtenances	1
b. Location	2
c. Size Classification	2
d. Hazard Classification	2
e. Ownership	2
f. Purpose of Dam	2
g. Design and Construction History	2
h. Normal Operational Procedure	2
1.3 Pertinent Data	3-4
 2. ENGINEERING DATA	
2.1 Design	5
2.2 Construction	5
2.3 Operation	5
2.4 Evaluation	5

<u>Section</u>	<u>Page</u>
3. VISUAL INSPECTION	
3.1 Findings	6
a. General	6
b. Dam	6
c. Appurtenant Structures	7
d. Reservoir Area	7
e. Downstream Channel	7
3.2 Evaluation	7
4. OPERATIONAL PROCEDURES	
4.1 Procedures	8
4.2 Maintenance of Dam	8
4.3 Maintenance of Operating Facilities	8
4.4 Description of any Warning System in Effect	8
4.5 Evaluation	8
5. HYDRAULIC/HYDROLOGIC	
5.1 Evaluation of Features	9
a. Design Data	9
b. Experience Data	10
c. Visual Observation	10
d. Overtopping Potential	10
6. STRUCTURAL STABILITY	
6.1 Evaluation of Structural Stability	11
a. Visual Observation	11
b. Design and Construction Data	11
c. Operating Records	11
d. Post-Construction Changes	11
e. Seismic Stability	11


SectionPage

7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES


7.1	Dam Assessment	12
a.	Condition	12
b.	Adequacy of Information	12
c.	Urgency	12
d.	Need for Additional Investigation	12
7.2	Recommendations	12
7.3	Remedial Measures	12
a.	Alternatives	12
b.	Operation and Maintenance and Procedures	13

LIST OF APPENDICES

<u>Appendix</u>	<u>Description</u>
I	Photographs
II	Hydrologic Computations
III	Visual Inspection - Check List
IV	Engineering Data - Check List
V	Drawings
IV	Information as Contained in the National Inventory of Dams



PUTNAM RESERVOIR DAM



PHASE I INSPECTION REPORT
PUTNAM RESERVOIR DAM CT 00041

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL:

a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a national program of dam inspection through the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Flaherty Giavara Associates, P.C. has been retained by the New England Division to inspect and report on selected dams in the State of Connecticut. Authorization and notice to proceed was issued to Flaherty Giavara Associates, P.C. under a letter of 25 April 1978 from Ralph T. Garver, Colonel, Corps of Engineers. Contract No. DACW33-78-C-0309 has been assigned by the Corps of Engineers for this work.

b. Purpose.

1) Perform technical inspection and evaluation of non-federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-federal interests.

2) Encourage and assist the States to initiate quickly effective dam safety programs for non-federal dams.

3) To update, verify and complete the National Inventory of Dams.

1.2 DESCRIPTION OF PROJECT:

a. Description of Dam and Appurtenances. Earth embankment with concrete core wall, built 1893, and modified in 1906 and 1922. The dam section is 640 feet long with a maximum height of 35 feet. The top of the dam is 30 feet wide. The downstream side slopes of the rolled earth embankment are 2 horizontal to 1 vertical. The upstream slope is 1-1/4 horizontal on 1 vertical. Riprap is in place on the upstream face. The spillway is 55 feet long, with an "Ogee" crest.

b. Location. The dam is located approximately 5 miles north of the Town of Greenwich on Horseneck Brook within the Connecticut western coastal area. The Putnam Lake water filtration plant is just downstream of the dam.

c. Size Classification. The applicable guideline indicates that for an intermediate category the storage in acre-feet for the impoundment must be greater than or equal to 1,000 and less than 50,000. The size classification may be determined by either storage or height, whichever gives the larger size category. Based on the storage capacity of the dam, the size classification is intermediate. The top of dam storage for Putnam Reservoir Dam is 1,775 acre-feet.

d. Hazard Classification. The dam is classified as having a high hazard potential. This classification is based on the 10 or more houses situated along the narrow valley through which Horseneck Brook flows and the fact that Haithcock School is located within the valley. Horseneck Brook also flows through a heavily built up commercial section of the Town of Greenwich.

e. Ownership. Putnam Reservoir Dam is owned by the Connecticut-American Waterworks Company, Inc. - Greenwich District.

f. Purpose of Dam. The dam was constructed to form an impounding reservoir. The reservoir forms part of the water company's supply and distribution system, providing potable water to the residents of Greenwich. The natural yield is augmented by flow from Rockwood Reservoir, which delivers through a 20-inch pipe 500 feet long, and by diversion from the east branch of the Byram River. Supply is diverted through an unlined tunnel, 4,191 feet in length to the upper end of Putnam Lake.

g. Design and Construction History. The dam was originally built in 1880, the dam was raised 5 feet in 1889, and 9.5 feet in 1910. The designers of the original dam and its subsequent modifications are unknown.

h. Normal Operating Procedures. Water is taken through the intake structure through three 24-inch by 36-inch sluice gates and delivered to the water filtration plant through a 30-inch diameter water supply main. A 24-inch blow off is provided.

1.3 PERTINENT DATA:

- a. Drainage Area - 2.1 sq. miles
- b. Discharge at Dam Site -
Maximum Known Flood Unknown
Warm Water Outlet Not Available
Div. Tunnel Low Pool Outlet None
Diversion Tunnel Outlet None
Gated Spillway None
Ungated Spillway at Max. Pool 1,000 CFS @ 1 Ft. freeboard
Total Spillway Cap. at Max. Pool 1,560 CFS @ no freeboard
- c. Elevation (above (M.S.L.)) -
Top of Dam 304
Max. Design Pool Not Available
Full Flood Control Pool Not Available
Recreation Pool Not Available
Spillway Crest Ungated 300
Upstream Portal Invert. Div. Tunnel Not Applicable
Downstream Portal Invert. Div. Tunnel Not Applicable
Streambed at Centerline of Dam 270
Maximum Tailwater 275+
- d. Reservoir -
Length of Max. Pool 4,800
Length of Recreation Pool Not Applicable
Length of Flood Control Pool Not Applicable
- e. Storage -
Recreation Pool Not Applicable
Flood Control Pool Not Applicable
Design Surcharge Not Applicable
Top of Dam 1,775 Acre-Feet
- f. Reservoir Surface (acres) -
Top of Dam Not Available
Max. Pool Not Available
Flood Control Pool Not Applicable
Recreation Pool Not Applicable
Spillway Crest 105
- g. Dam -
Type: Earth embankment, concrete core
Length: 640 feet
Height: 35 feet
Top width: 30 feet
Side slopes: Downstream: 1 vertical to 2 horizontal
Upstream: 1 vertical to 1-1/4 horizontal
Zoning: Rolled earth shell

Impervious core: Concrete core
Grout Curtain: Unknown

h. Diversion and Regulating Tunnel -

Type: Not Applicable
Length: Not Applicable
Diameter: Not Applicable
Access: Not Applicable
Regulation: Not Applicable

i. Spillway -

Type: Ogee
Length of Weir: 50 feet
Crest Elevation: 300
Gates: Ungated
Upstream Channel: Reservoir
Downstream Channel: Concrete lined, bedrock bottom
Spillway is founded on: Unknown

j. Regulating Outlets -

Gates: 3 24-inch x 36" sluice gates
Conduits: 30" diameter cast iron pipe to water
filtration plant
24" drain cast iron pipe to blow off/drain

SECTION 2 - ENGINEERING DATA

2.1 DESIGN:

No engineering data has been found to provide any information about the design of the Putnam Lake Dam.

2.2 CONSTRUCTION:

A sketch map showing a plan view of the dam, a section through the proposed dam and a plan for a new gate house (all undated) are the only known construction information available. Information presented in this report was primarily obtained by interviews and direct measurements of the existing structures.

2.3 OPERATION:

Formal operation records are not available for this dam.

2.4 EVALUATION:

a. Availability. Only minimal engineering information is available for this dam.

b. Adequacy. The adequacy of design, construction and operation cannot be evaluated.

c. Validity. There is no reason to question the validity of the available data.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS:

a. General. The downstream embankment slope appeared to be in good condition. A slight bulge was noted near mid-slope at the western portion of the dam. No seepage or wet areas were noted. The crest was level. The upstream embankment and riprap were in good condition. The spillway section was in disrepair, with major spalling, vertical cracks, and several wet spots noted. Water was not passing over the spillway during the inspection (June 14, 1978). The Gate House and operating facilities were in good condition. All valves were operated with the exception of the blow-off valve. Water company personnel did not allow operation since they were concerned with low flow conditions in the outlet and the possibility of rusty blow-off piping. Inspection personnel were unable to locate the blow-off control.

b. Dam.

1) Upstream Slope - At the time of the visual inspection of the dam, the reservoir level was approximately 1 foot below the spillway crest, and thus only the upper few feet of slope could be observed. The riprap protection inspected was generally in good shape with an occasional small window exposed through the riprap. Near Station 7+00 on the left side of the dam, there is some erosion and settling of the riprap.

2) Crest - The condition of the crest was generally good with the exception of two small ruts near the centerline of the crest which were apparently due to foot traffic and motor bikes.

3) Downstream Slope - No evidence of seepage or wet areas were found on the downstream slope or downstream of the dam adjacent to the existing road. Several small animal holes were located near the toe of the slope in the vicinity of Station 1+60 and Station 3+00. The slope appeared in good shape with only a small bulge in the vicinity of Station 2+25 near mid-slope.

4) Spillway - The spillway has extensive spalling throughout most of the downstream face. There are several vertical cracks in the downstream face, and an eroded hole in the top of the spillway. There were several wet spots noted on the face of the spillway at the horizontal construction joints which indicate that water is seeping through the concrete section. There is a vertical crack in the east wall from the top of the wall to its junction with the spillway on its upstream face.

c. Appurtenant Structures. The intake structure appears to be in good condition. All gates and valves were cracked open and are operable. The 24-inch blow-off was not operated during the visual inspection, although a request was made to attempt operation of the valve. All visible electrical facilities were in good condition, free of dirt and corrosion.

d. Reservoir Area. The reservoir has well vegetated banks at slight to moderate slopes. There was no indication of slides or sloughing. The depth of sediment and rate of accumulation in the reservoir are unknown.

e. Downstream Channel. The spillway channel is 30 to 50 feet wide, has a rough rock bottom, and both concrete and stone-mortar vertical walls. The channel directs flow into a culvert which passes underneath the adjacent roadway. Both walls are in fairly good condition with several small seeps coming from the base of the east wall. The channel contains many large boulders and there are some tree branches which have fallen into the channel. Overhanging trees and brush growth can result in additional trees and branches falling into the channel.

3.2 EVALUATION:

Visual observation revealed that the dam and attendant structures are structurally sound and that no immediate actions to remedy any serious problems should be taken.

a. The spillway section shows considerable deterioration and stress and this condition should be corrected before it becomes hazardous.

b. The seeps along the base of the training wall are not considered to have an adverse effect on the structural integrity of the dam at this time, but should be closely monitored to insure that any future flow increase be observed.

c. Animal holes in the embankment and toe should be filled and plugged.

d. The bottom of the spillway channel which contains tree branches and other debris can reduce its flow capacity.

e. The control valve for the 24-inch diameter blow off should be located, and exercised on a regular basis.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 PROCEDURES:

Water is taken from Putnam Lake through the gate house to the filtration plant just downstream. The plant at Putnam Lake can provide 17 mgd (peak capacity) to customers in Greenwich. It was reported that the intake point from the lake is periodically changed, however, the blow-off is operated only once a year at high flow conditions.

4.2 MAINTENANCE OF DAM:

The dam is well maintained with a regular program of grass mowing and general maintenance in effect. The associated spillway structure needs maintenance to insure continued safe serviceability.

4.3 MAINTENANCE OF OPERATING FACILITIES:

The regulating gates and valves were tested and appear to be in mechanically good operating condition and are completely functional. The blow-off valve was not located due to overgrown condition.

4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT:

There was no warning system of any kind in effect at the time of the inspection. The Connecticut-American Waterworks Company is currently developing procedures which will provide for surveillance during peak flow conditions and a warning system.

4.5 EVALUATION:

The Putnam Reservoir Dam which is over 70 years old is well operated and maintained. Although not designed for rapid drawdown, it should be noted that if the need should arise, drawdown could be effected only through the operational procedure of opening the 24-inch blow-off. Therefore, this valve should be located and periodically exercised to insure proper functioning.

SECTION 5 - HYDRAULICS/HYDROLOGY

5.1 EVALUATION OF FEATURES:

a. Design Data. There is no available information on the hydraulic design criteria for this dam and appurtenances. Under established criteria (OCE Guidelines) the recommended spillway design flood for the size (intermediate) and hazard potential (high) classification is the probable maximum flood (PMF). The PMF is the flood that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region. The PMF is the applicable "test flood" for this dam.

An estimate of the magnitude of the test flood at the site is based on an analysis of several sets of regional flood frequency data as presented in Appendix II.

As a conservative approach to the investigation, the more critical design hydrograph was used throughout. The peak discharge of the test flood of 4,400 CFS was therefore utilized.

A stage-discharge relationship was calculated for the spillway and indicates the following flows, based upon a coefficient of 3.9 and a length of 50 feet.

Stage - Discharge Relationship

<u>Stage</u>	<u>Head, Ft.</u>	<u>Discharge Rate, CFS</u>
301	1	190
302	2	550
303	3	1,010
304	4	1,560

The maximum spillway capacity, with no freeboard, is 35 percent of the peak inflow rate of the test flood. (Compare 4,400 CFS with 1,560 CFS.) In order to determine the effect of the reservoir storage capacity, a hydrograph of the test flood was routed through the reservoir.

The hydrograph was formed by assuming the test flood had a duration of 24 hours, with the peak of 4,400 CFS occurring at 8 hours from the beginning of runoff. The rising and falling limbs of the hydrograph were assumed to be changing at a constant rate, forming a triangle. The routing operation indicated that the peak rate of discharge would not be reduced and would result in a stage elevation of 305.1 (1.1 feet above top of dam).

b. Experience Data. During major storm events all augmenting flow from the Byram River diversion is eliminated. Discussion with water company personnel indicate that since 1950 the dam has safely discharged the floods that have hit the western Connecticut coastal area. The maximum stage was reported to have been about 18 inches above the top of the spillway (elevation 301.5 MSL).

c. Visual Observations. The on-site inspection of the dam provided the data for the hydraulic/hydrologic evaluation of the spillway.

d. Overtopping Potential. The maximum spillway capacity is equal to less than one-half the test flood. The peak rate of discharge would overtop the embankment (1.1 feet). For a test flood duration of 24 hours, the embankment would be overtopped for an 8-hour period.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY:

a. Visual Observations. No evidence was observed indicating structural instability of the embankment dam. The concrete spillway section showed signs of deterioration, including major spalling, cracking and seepage.

b. Design and Construction Data. Sufficient data is not available on the soil properties and design and construction of the earth embankment to permit a formal evaluation of stability. No stability analyses calculations were available for the concrete spillway section.

c. Operating Records. No recorded information was reviewed that indicated a stability problem. No major operational problems were reported, notwithstanding the several tropical storms and hurricanes since that time. As the Putnam Dam is used as a water supply dam and has been subjected to a full head of water most of the time, its stability is considered to be adequate based on performance.

d. Post-construction Changes. Storm drainage facilities have been constructed on the roadway just south of the dam embankment. No evidence indicates that this construction has had a detrimental effect on dam stability. Records indicate that the dam height was raised in 1889 and again in 1910.

e. Seismic Stability. This dam is in Seismic Zone 1, and therefore a seismic analysis is not warranted.

SECTION 7 - ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 DAM ASSESSMENT:

a. Condition. Based on the visual inspection, records available and past operational performance, the dam is judged to be in good condition.

The overtopping potential analysis shows that the dam will be overtopped by the test flood. The spillway capacity therefore is inadequate. The project will pass 35 per cent of the test flood without overtopping and thus the spillway capacity is considered seriously inadequate.

b. Adequacy of Information. The information available is such that the evaluation of the dam must be based primarily on the visual inspection and the past operational performance of the structure.

c. Urgency. The recommendations and remedial measures recommended should be implemented by the owner in the near term.

d. Need for Additional Investigation. A detailed investigation to further assess the requirements for obtaining additional spillway capacity is necessary.

7.2 RECOMMENDATIONS:

It is recommended that the following measures be undertaken by the owner:

1) Detailed investigations be initiated to determine the requirements and methods for obtaining additional spillway capacity.

2) Surface spalling and cracking of the spillway should be repaired in order to prevent continued deterioration and a potentially hazardous condition.

3) Boulders, debris, overhanging trees which were observed to be obstructing both the outlet channel and discharge spillway channel should be removed.

7.3 REMEDIAL MEASURES:

Although the dam is generally maintained in good condition, it is considered important that the following items be accomplished:


a. Alternatives. Not applicable.

b. Operation and Maintenance and Procedures.

- 1) Arrangements should be made to locate, operate and maintain the blow-off control valve.
- 2) Animal holes in the embankment and toe should be filled and plugged.
- 3) The seepage in the outlet channel should be monitored to determine any increase in discharge.
- 4) Operation and maintenance manual for the project should be prepared.
- 5) A program of periodic inspections of the project features should be established.
- 6) In periods of unusually high runoff an around the clock surveillance and warning program should be exercised.

APPENDIX I

PHOTOGRAPHS



PUTNAM RESERVOIR DAM
LOCATION OF PHOTOGRAPHS



PHOTO #1: Upstream Face of Dam, looking East.



PHOTO #2: Upstream Face of Dam, looking West.




PHOTO #3: Upstream Face of Spillway.



PHOTO #4: Downstream Face of Spillway. Note Concrete Spalling.



PHOTO #5: Intake Structure and Gate House.



PHOTO #6: Stone Conduit housing the Blow-off Discharge Point.
Note flow from 2-inch diameter drain near center of photo.



PHOTO #7: Riprap on Upstream Face of Dam, looking West from Intake Structure.



PHOTO #8: Riprap detail at Sta. 7+00. Note extent of coverage.



PHOTO #9: View of Earth Embankment, looking East from Spillway Discharge Channel.



PHOTO #10: Spillway Discharge Channel, looking downstream.




PHOTO #11: View of Animal Burrow Holes at Toe of Earth Embankment.



PHOTO #12: Downstream Face of Embankment. Note "bulge" in the slope at Sta. 2+20.



PHOTO #13: Culvert to carry Spillway Discharges under the road South of the Dam.





PHOTO #14: Drain Hole in East wall of Spillway Discharge Channel.

APPENDIX II
HYDROLOGIC COMPUTATIONS



SCALE IN FEET
6000 0 3000 6000

DRAINAGE AREA MAP
PUTNAM RESERVOIR DAM
GREENWICH, CONNECTICUT

RUTNAM
RESERVOIR
DAM



FLAHERTY-GIAVARA ASSOCIATES
ENVIRONMENTAL DESIGN CONSULTANTS
ONE COLUMBUS PLAZA, NEW HAVEN, CONN. 06510/203/789-1260

SHEET NO. 1 OF 2
BY JGM DATE 7/5/77
CHK'D BY RCS DATE 8/1/77

PMF. PEAK FLOW ESTIMATE

WATERSHED AREA IS 2.1 SQUARE MILES

METHOD #1

REFER TO "PRELIMINARY GUIDANCE FOR
ESTIMATING PMF DISCHARGES" by
NEW ENGLAND DIVISION, CORPS OF ENGINEERS

UNIT FLOW = 2100 CFS/MI² (ROLLING)
PMF $\approx 2.1 \text{ MI}^2 (2100 \text{ CFS}) = 4410 \text{ CFS}$
SAY $\approx 4400 \text{ CFS}$

METHOD #2

REFER TO "CONN WATER RESOURCE
BULLETIN #17, PART 4" by USGS

MEAN ANNUAL FLOOD = 120 CFS (FIG 13)
 $Q_{100} = 5 \times \text{MAF} = 5(120) = 600 \text{ CFS}$ (FIG 14)

PMF $\approx 5 \times Q_{100}$ (APPROXIMATE)
PMF $\approx 5 \times 600 \text{ CFS} = 3000 \text{ CFS}$

METHOD #3

REFER TO FAIRFIELD, CT FLOOD INSURANCE
STUDY, = FREQUENCY DISCHARGE,
DRAINAGE AREA CURVES

$Q_{100} = 950 \text{ CFS}$ (FIG. 2)
PMF $\approx 5 \times Q_{100} \approx 5 \times (950 \text{ CFS}) = 4750 \text{ CFS}$

FOR SPILLWAY EVALUATION, USE 4400 CFS



FORMATION OF INFLOW HYDROGRAPH

- 1) P.M.F. \approx 4400 CFS (see previous sheet)
- 2) FORM A TRIANGULAR HYDROGRAPH
24 HOURS DURATION, PEAK AT 8 HOURS

<u>TIME HOURS</u>	<u>UNIT FLOW RATE</u>	<u>FLOW RATE CFS</u>
0	0.00	0
2	0.25	1100
4	0.50	2200
6	0.75	3300
8	1.00	4400
10	0.875	3850
12	0.75	3300
16	0.50	2200
20	0.25	1100
24	0.00	0

JTNAM DAN

78-36-10

FLOOD ROUTING

JGM

7/13/78

INPUT DATA:

SEGMENT 1
SEGMENT 2
IV=UNSUBMERGED WEIR
DISCHARGE COEFFICIENT = 3.9
DISCHARGE COEFFICIENT = 3
E=300 A=105.00 E=310
A=105.00LENGTH OF WEIR = 50
LENGTH OF WEIR = 640ELEVATION OF WEIR = 300
ELEVATION OF WEIR = 304

HOOR	INFLOW	MASS INFLOW	WATER EL.	TAIL WATER	OUTFLOW	MASS OUTFLOW	STORAGE(R)	STORAGE(A)
0.00	0CFS	0.00AC-F	300.00FT	0.00FT	0CFS	0.00AC-F	0.00AC-F	0.00AC-F
2.00	1,100CFS	90.90AC-F	300.76FT	0.00FT	130CFS	10.74AC-F	80.15AC-F	80.16AC-F
4.00	2,200CFS	363.63AC-F	302.61FT	0.00FT	822CFS	89.48AC-F	274.14AC-F	274.14AC-F
6.00	3,300CFS	818.18AC-F	304.43FT	0.00FT	352.84CFS	465.33AC-F	465.33AC-F	465.33AC-F
8.00	4,400CFS	1,454.54AC-F	305.10FT	0.00FT	918.49CFS	536.05AC-F	536.05AC-F	536.05AC-F
10.00	3,850CFS	2,136.36AC-F	304.95FT	0.00FT	1,615.69CFS	520.67AC-F	520.67AC-F	520.67AC-F
12.00	3,300CFS	2,727.27AC-F	304.79FT	0.00FT	2,223.94CFS	503.33AC-F	503.33AC-F	503.33AC-F
16.00	2,200CFS	3,636.36AC-F	304.41FT	0.00FT	3,172.31CFS	464.05AC-F	464.05AC-F	464.05AC-F
20.00	1,100CFS	4,181.81AC-F	303.72FT	0.00FT	4,404CFS	391.62AC-F	391.62AC-F	391.62AC-F
24.00	0CFS	4,363.63AC-F	302.22FT	0.00FT	648CFS	234.02AC-F	234.02AC-F	234.02AC-F
30.00	0CFS	4,363.63AC-F	300.52FT	0.00FT	73CFS	54.88AC-F	54.88AC-F	54.88AC-F
36.00	0CFS	4,363.63AC-F	300.28FT	0.00FT	28CFS	29.43AC-F	29.43AC-F	29.43AC-F
48.00	0CFS	4,363.63AC-F	300.11FT	0.00FT	7CFS	11.55AC-F	11.55AC-F	11.55AC-F

APPENDIX III
VISUAL INSPECTION
CHECK LIST

PERIODIC INSPECTION CHECK LIST

PROJECT _____

DATE _____

INSPECTOR _____

DISCIPLINE _____

INSPECTOR _____

DISCIPLINE _____

AREA EVALUATED	CONDITION
<p><u>CONCRETE DAM STRUCTURE</u></p> <p>General Condition Concrete Surfaces</p> <p>Movement or Settlement of Crest</p> <p>Vertical Alignment</p> <p>Horizontal Alignment</p> <p>Condition at Abutment and Other Structures</p> <p>Structural Cracking</p> <p>Spalling</p> <p>Visible Reinforcing</p> <p>Rusting or Staining of Concrete</p> <p>Condition of Monolith/ Construction Joints</p> <p>Drains - Foundation, Joint, Faces</p> <p>Any Seepage or Efflorescence</p> <p>Foundation Damage, Undermining</p> <p>Water Passages</p> <p>Abutments</p>	

PERIODIC INSPECTION CHECK LIST

PROJECT Putnam Reservoir Dam

DATE June 14, 1978

INSPECTOR Richard Murdock

DISCIPLINE Geotechnical

INSPECTOR _____

DISCIPLINE _____

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	304 ₊
Current Pool Elevation	299 ₊
Maximum Impoundment to Date	301.5 ₊
Surface Cracks	None observed
Pavement Condition	Shallow ruts along crest due to foot traffic
Movement or Settlement of Crest	None observed
Lateral Movement	None observed
Vertical Alignment	Good
Horizontal Alignment	Good
Condition at Abutment and at Concrete Structures	Good
Indications of Movement of Structural Items on Slopes	None observed
Trespassing on Slopes	A few small stumps were observed near Sta. 2+50
Sloughing or Erosion of Slopes or Abutments	A few woodchuck holes were observed on slope. One large hole was observed near Sta. 2+90.
Rock Slope Protection - Riprap Failures	Riprap has a few small open windows.
Unusual Movement or Cracking at or near Toes	None observed
Unusual Embankment or Downstream Seepage	None observed

PERIODIC INSPECTION CHECK LIST

PROJECT Putnam Reservoir Dam

DATE June 14, 1978

INSPECTOR Richard Murdock

DISCIPLINE Geotechnical

INSPECTOR _____

DISCIPLINE _____

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u> - (continued)	
Piping or Boils	None observed
Foundation Drainage Features	None
Toe Drains	None
Instrumentation System	None

PERIODIC INSPECTION CHECK LIST

PROJECT Putnam Reservoir Dam

DATE June 14, 1978

INSPECTOR Anthony Rummo

DISCIPLINE Structural

INSPECTOR James MacBroom

DISCIPLINE Hydraulics/
Hydrology

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - CONTROL TOWER</u></p> <p>a. Concrete and Structural</p> <p>General Condition</p> <p>Condition of Joints</p> <p>Spalling</p> <p>Visible Reinforcing</p> <p>Rusting or Staining of Concrete</p> <p>Any Seepage or Efflorescence</p> <p>Joint Alignment</p> <p>Unusual Seepage or Leaks in Gate Chamber</p> <p>Cracks</p> <p>Rusting or Corrosion of Steel</p> <p>b. Mechanical and Electrical</p> <p>Air Vents</p> <p>Float Wells</p> <p>Crane Hoist</p> <p>Elevator</p> <p>Hydraulic System</p>	<p>The control tower is in good condition.</p>

PERIODIC INSPECTION CHECK LIST

PROJECT Putnam Reservoir Dam

DATE June 14, 1978

INSPECTOR Anthony Rummo

DISCIPLINE Structural

INSPECTOR James MacBroom

DISCIPLINE Hydraulics/
Hydrology

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - CONTROL TOWER</u> (continued)</p> <p>Service Gates</p> <p>Emergency Gates</p> <p>Lightning Protection System</p> <p>Emergency Power System</p> <p>Wiring and Lighting System In Gate Chamber</p>	<p>All gates and valves were operable and in good condition. Blow-off valve not operated.</p> <p>Good condition</p>

PERIODIC INSPECTION CHECK LIST

PROJECT Putnam Reservoir Dam

DATE June 14, 1978

INSPECTOR _____

DISCIPLINE _____

INSPECTOR _____

DISCIPLINE _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u> a. Approach Channel Slope Conditions Bottom Conditions Rock Slides or Falls Log Boom Debris Condition of Concrete Lining Drains or Weep Holes b. Intake Structure Condition of Concrete Stop Logs and Slots	

PERIODIC INSPECTION CHECK LIST

PROJECT Putnam Lake Dam

DATE June 14, 1978

INSPECTOR Richard Murdock

DISCIPLINE Geotechnical

INSPECTOR Anthony Rummo

DISCIPLINE Structural

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	
General Condition	
Loose Rock Overhanging Channel	
Trees Overhanging Channel	
Floor of Approach Channel	
b. Weir and Training Walls	
General Condition of Concrete	Highly eroded, cracking and generally poor condition
Rust or Staining	
Spalling	Major spalling
Any Visible Reinforcing	None
Any Seepage or Efflorescence	Seepage noted through face of spillway
Drain Holes	None
c. Discharge Channel	
General Condition	
Loose Rock Overhanging Channel	None
Trees Overhanging Channel	Several trees adjacent to west side of channel
Floor of Channel	Loose rock, logs, debris
Other Obstructions	None

PERIODIC INSPECTION CHECK LIST

PROJECT _____

DATE _____

INSPECTOR _____

DISCIPLINE _____

INSPECTOR _____

DISCIPLINE _____

AREA EVALUATED

CONDITION

OUTLET WORKS - TRANSITION AND CONDUIT

General Condition of Concrete

Rust or Staining on Concrete

Spalling

Erosion or Cavitation

Cracking

Alignment of Monoliths

Alignment of Joints

Numbering of Monoliths

PERIODIC INSPECTION CHECK LIST

PROJECT Putnam Reservoir Dam

DATE June 14, 1978

INSPECTOR Richard Murdock

DISCIPLINE Geotechnical

INSPECTOR _____

DISCIPLINE _____

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u></p> <p>General Condition of Concrete</p> <p>Rust or Staining</p> <p>Spalling</p> <p>Erosion or Cavitation</p> <p>Visible Reinforcing</p> <p>Any Seepage or Efflorescence</p> <p>Condition at Joints</p> <p>Drain Holes</p> <p>Channel</p> <p>Loose Rock or Trees Overhanging Channel</p> <p>Condition or Discharge Channel</p>	<p>Debris, loose rock, some brush overhanging right training wall.</p> <p>One small seep was observed near Sta. 1+07 at the toe of the left training wall at approximately El. 288.</p>

PERIODIC INSPECTION CHECK LIST

PROJECT Putnam Reservoir Dam

DATE June 14, 1978

INSPECTOR Anthony Rummo

DISCIPLINE Structural

INSPECTOR _____

DISCIPLINE _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SERVICE BRIDGE</u>	
a. Super Structure	
Bearings	Both service bridges, (across top of spillway, dam to inlet structure) show some rusting but are in good condition.
Anchor Bolts	
Bridge Seat	
Longitudinal Members	
Under Side of Deck	
Secondary Bracing	
Deck	
Drainage System	
Railings	
Expansion Joints	
Paint	
b. Abutments & Piers	
General Condition of Concrete	Generally good condition
Alignment of Abutment	
Approach to Bridge	
Condition of Seat & Backwall	Crack at west and east end (spillway) considerable spalling of concrete wall east side

APPENDIX IV

ENGINEERING DATA

CHECK LIST

CHECK LIST
 ENGINEERING DATA
 DESIGN, CONSTRUCTION, OPERATION
 PHASE I

NAME OF DAM Putnam Reservoir Dam
 I.D. NO. 41

ITEM	REMARKS
AS-BUILT DRAWINGS	None exist
REGIONAL VICINITY MAP	From U.S.G.S.
CONSTRUCTION HISTORY	Not available
TYPICAL SECTIONS OF DAM	Sketch Map
OUTLETS - Plan	None available
- Details	None available
- Constraints	Unknown
- Discharge Ratings	None
RAINFALL/RESERVOIR RECORDS	None
DESIGN REPORTS	None
GEOLOGY REPORTS	None
DESIGN COMPUTATIONS	None
HYDROLOGY & HYDRAULICS	None
DAM STABILITY	None
SEEPAGE STUDIES	None
MATERIALS INVESTIGATIONS	None
BORINGS RECORDS	None
LABORATORY	None
FIELD	None



CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION
PHASE I

NAME OF DAM Putnam Reservoir Dam
I.D. NO. 41

ITEM	REMARKS
POST-CONSTRUCTION SURVEYS OF DAM	None
BORROW SOURCES	Unknown
MONITORING SYSTEMS	None
MODIFICATIONS	Sketch Map
HIGH POOL RECORDS	None
POST-CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None
MAINTENANCE OPERATION RECORDS	From Connecticut American Waterworks Company
SPILLWAY PLAN	
SECTIONS	From field measurements
DETAILS	None
OPERATING EQUIPMENT PLANS & DETAILS	None


APPENDIX V

DRAWINGS




DOWNSTREAM EL

NT




PLAN
NTS



DAM ELEVATION OF DAM
NTS

PUTNAM RESERVOIR DAM
HORSENECK BROOK

II



SECTION OF DAM AND GATE HOUSE

NTS

PUTNAM RESERVOIR DAM
HORSENECK BROOK

APPENDIX VI
INFORMATION AS CONTAINED IN
THE NATIONAL INVENTORY OF DAMS

INVENTORY OF DAMS IN THE UNITED STATES

STATE	DIVISION	COUNTY	CITY	NAME	REPORT DATE
CT	41	NED	CT 001 04	PUTNAM RESERVOIR DAM	18 AUG 78

POPULAR NAME	NAME OF IMPOUNDMENT
PUTNAM LAKE	PUTNAM RESERVOIR

REGION/DAM	RIVER OR STREAM	NEAREST DOWNSTREAM CITY-TOWN-VILLAGE	DIST FROM DAM (MI.)	POPULATION
01 07	HORSENECK BROOK	GREENWICH	4	60100

TYPE OF DAM	YEAR COMPLETED	PURPOSES	STRUCTURAL HEIGHT (FT.)	HYDRAULIC HEIGHT (FT.)	IMPOUNDING CAPACITIES (ACRE-FT.)
HEPG	1910	S	39	37	1775

DIST OWN FED R PRV/FED SCS A VER/DATE
N N N N N 16AUG78

REMARKS

TOUS	SPILLWAY	MAXIMUM DISCHARGE (FT.)	VOLUME OF DAM (CY)	POWER CAPACITY (KW)	NAVIGATION LOCKS
1	640 U 50	1560	43000	37	1775

OWNER	ENGINEERING BY	CONSTRUCTION BY
CUNN AMEN WATERWORKS CO		

DESIGN	CONSTRUCTION	OPERATION	MAINTENANCE
NONE	NONE	NONE	NONE

INSPECTION BY	INSPECTION DATE	AUTHORITY FOR INSPECTION
FLAMERTY-GIAVARA, ASSOC, PC	14 JUN 78	PL 92 367

REMARKS

END

FILMED

8 74

DTIC